
# LABC Registered Construction Details Masonry



### **Registration Number: E7MCFF2**



#### **Build Up**

**External Masonry Cavity Wall** 

Masonry Outer Leaf ( $\lambda = 0.77$ )

Lightweight Concrete Block λ ≤ 0.60 W/mK

**Full Fill Insulation** 

**Precast Concrete Floor Between Dwellings** 









# LABC Registered Construction Details Masonry



### **Calculated ψ-values**

	Inner leaf blockwork
	Lightweight Concrete Block λ ≤ 0.60 W/mK
<b>Cavity Insulation</b>	ψ-value W/mK
<b>100mm</b> λ=0.037	0.105
100mm λ=0.032	0.093
<b>150mm</b> λ=0.037	0.074
150mm λ=0.032	0.065

<sup>\*</sup> Half the  $\psi$ -value shown should be applied to each dwelling

#### **Points to Watch**

- Ensure cavities are kept clean of mortar snots and other debris during construction.
- Seal between the wall air barrier and the floor above and below the connection with a flexible sealant.
- Separating floors require additional layers and components to comply with Fire and Noise requirements.
- This detail conforms with the MIMA good practice guide, when full fill insulation is used the cavity barrier is NOT a requirement of Approved Document Part B.
- Cavity barriers may require an additional vertical DPC and/or cavity tray.







